

Terna Public Charitable Trust
Comound wall fabrication work for plot boundries of 12A and 12 B
Bill of Quantities

Sr. No.	Descreption	Quantity	Unit	Rate	Amount
	Compound Wall Fabrication Work Option 01				
1	Fabrication work (Solid Verical Rod) :- (Rates are inclusive of all taxes) Providing and fabricating structural steel work of in Mild Steel solid as per detailed design and drawings or as directed by Engineer- In- Charge. Including cutting, fabricating, hoisting, erecting, fixing in position welded connections with connecting plates, braces ,nuts ,bolts, anchor fastener,drilling, rawal plug and other neccessary fixture and fastening.etc. and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade etc. complete.	55520	kg		
	Compound Wall Fabrication Work Option 02				
2	Fabrication work (Hollow Verical Rod) :- (Rates are inclusive of all taxes) Providing and fabricating structural steel work of in Mild Steel hollow as per detailed design and drawings or as directed by Engineer- In- Charge. Including cutting, fabricating, hoisting, erecting, fixing in position welded connections with connecting plates, braces ,nuts ,bolts, anchor fastener,drilling, rawal plug and other neccessary fixture and fastening.etc. and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade etc. complete.	40621	Kg.		
3	Spike above vertical rod:- (Rates are inclusive of all taxes) Providing and fabricating structural steel work of in Cast Iron spike as per detailed design and drawings or as directed by Engineer- In- Charge. Including cutting, fabricating, hoisting, erecting, fixing in position welded connections with connecting plates, braces etc. and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade etc. complete.	4200	Nos		
		Total Alternate 1 + 3			
		Total Alternate 2 + 3			